



TYPE "A" CURB AND GUTTER



TYPE "B" CURB

CURBS




AC BERM

NOTE:

1. CONSTRUCT TYPE "A" CURB AND GUTTER WITH 10' BUFFER TO CONFORM GUTTER TO EXISTING CONDITIONS.
2. SAWCUT APPROXIMATELY 1' FROM THE EDGE OF CURB ON THE ROADWAY SIDE TO ALLOW SPACE FOR CONSTRUCTION. PLUG GAP WITH NEW ASPHALT CONCRETE.
3. WHEN POSSIBLE USE TYPE "A" CURB AND GUTTER WITH SIDEWALK AND TYPE "B" CURB WHEN CONSTRUCTING MEDIANS AT CENTER OF ROADWAY. AC BERM USED AT THE APPROVAL OF THE CITY ENGINEER.

SCALE: NTS





CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**AC DIKE, CURB AND GUTTER
DETAIL**

STD DETAIL No.
ST 1



SECTION A-A




SECTION B-B

NOTES:

1. CONSTRUCT DRIVEWAY TYPE 2 TO CONFORM TO EXISTING DRIVEWAY, SIDEWALK AND CURB AND GUTTER
2. CONFORM TO WIDTHS OF SIDEWALKS AND CURB AND GUTTER WIDTHS AND HEIGHTS. WHENEVER POSSIBLE MAINTAIN MINIMUM WIDTH OF 5' FOR SIDEWALKS, 1'-6" FOR GUTTERS AND 6" FOR CURB HEIGHTS.

SCALE: NTS





CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

DRIVEWAY TYPE 1

STD DETAIL No.
ST 2



SECTION A-A



SECTION B-B

NOTES:

1. CONSTRUCT DRIVEWAY TYPE 2 TO CONFORM TO EXISTING DRIVEWAY, SIDEWALK AND CURB AND GUTTER
2. CONFORM TO WIDTHS OF SIDEWALKS AND CURB AND GUTTER WIDTHS AND HEIGHTS. WHENEVER POSSIBLE MAINTAIN MINIMUM WIDTH OF 5' FOR SIDEWALKS, 1'-6" FOR GUTTERS AND 6" FOR CURB HEIGHTS.
3. FOR DRIVEWAY CONFORM MATCH THE SAME MATERIAL AS THE EXISTING DRIVEWAY.

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

DRIVEWAY TYPE 2


STD DETAIL No.
ST 3



SIDEWALK - TYPE I



SIDEWALK - TYPE II (MONOLITHIC SIDEWALK AND CURB & GUTTER)




NOTES

1. FOR NEW SIDEWALK MINIMUM WIDTH IS 5' UNLESS APPROVED BY CITY ENGINEER. WHEN PLACING SIDEWALK CONFORM TO EXISTING WIDTH OF SIDEWALK. TYPE 1 WIDTH MEASURED FROM FRONT OF SIDEWALK TO BACK OF SIDEWALK. TYPE 2 WIDTH MEASURED FROM FACE OF CURB TO BACK OF SIDEWALK.

SCALE: NTS

CITY OF ALBANY, CALIFORNIA


STANDARD



APPROVED BY: *Mal V. Buckley*
DATE: MARCH 2022

SIDEWALK: TYPE I AND II


STD DETAIL No.
ST 4.0



NOTES:

1. CONSULT WITH CITY ENGINEER IN LOCATIONS WHERE EXISTING CONDITIONS PREVENT BACK OF SIDEWALK CURVATURE.
2. CONSULT WITH CITY ENGINEER IN LOCATIONS WHERE 12" MINIMUM WIDTH BETWEEN STREET TREE AND SIDEWALK IS NOT FEASIBLE.
3. MAINTAIN MINIMUM 3' OF PLANTER SPACE BETWEEN STREET TREE AND EXISTING CONDITIONS. REMOVE EXISTING ASPHALT OR CONCRETE IF PRESENT. DO NOT ALTER DRIVEWAY OR CURB RAMP IF WITHIN 3' OF STREET TREE UNLESS APPROVED BY CITY ENGINEER.
4. FOR ADDITIONAL REQUIREMENTS, SEE ST 4.0
5. CONSULT WITH CITY ENGINEER WHERE PLANTER WIDTH IS LESS THAN 4'
6. CONSULT WITH CITY ENGINEER WHERE SIDEWALK WIDTH IS LESS THAN 4'.

SCALE: 1/4"=1'-0"



CITY OF ALBANY, CALIFORNIA


STANDARD

APPROVED BY: *Mal V. Buckley*

DATE: MARCH 2022

**SIDEWALK (WHERE WIDTH ≥ 4 FT & < 5 FT)
CURVATURE AROUND STREET TREE**

STD DETAIL No.
ST 4.1



NOTES:

1. CONSULT WITH CITY ENGINEER IN LOCATIONS WHERE EXISTING CONDITIONS PREVENT BACK OF SIDEWALK CURVATURE.
2. CONSULT WITH CITY ENGINEER IN LOCATIONS WHERE 12" MINIMUM WIDTH BETWEEN STREET TREE AND SIDEWALK IS NOT FEASIBLE.
3. MAINTAIN MINIMUM 3' OF PLANTER SPACE BETWEEN STREET TREE AND EXISTING CONDITIONS. REMOVE EXISTING ASPHALT OR CONCRETE IF PRESENT. DO NOT ALTER DRIVEWAY OR CURB RAMP IF WITHIN 3' OF STREET TREE UNLESS APPROVED BY CITY ENGINEER.
4. FOR ADDITIONAL REQUIREMENTS, SEE ST 4.0
5. CONSULT WITH CITY ENGINEER WHERE PLANTER WIDTH IS LESS THAN 4'

SCALE: 1/4"=1'-0"

CITY OF ALBANY, CALIFORNIA

STANDARD



APPROVED BY: *Mal V. Buckley*
 DATE: MARCH 2022

**SIDEWALK (WHERE WIDTH ≥ 5FT)
 CURVATURE AROUND STREET TREE**

STD DETAIL No.
ST 4.2

CURB RAMP
SEE ST-9

ECR

SCORE MARK (SEE
NOTE 4)

EDGE
DRIVEWAY
(REFER TO ST 2 AND/OR
ST 3 FOR DRIVEWAY DETAILS)

BCR

UTILITY
POLE

NOTES:

1. WEAKENED PLANE JOINTS SHALL BE USED FOR ALL JOINTS, EXCEPT EXPANSION JOINTS SHALL BE PLACED IN CURB, GUTTER AND SIDEWALK AT THE BCR AND ECR, AND AROUND UTILITY POLES LOCATED IN SIDEWALK AREAS AND AT 200' SPACING.
2. CURB AND GUTTER MAY BE CONSTRUCTED MONOLITHICALLY OR SEPARATELY FROM SIDEWALK.
3. WEAKENED PLANE JOINTS SHALL BE CONSTRUCTED AT REGULAR INTERVALS, NOT EXCEEDING 10 FEET IN WALKS OR 20 FEET IN GUTTERS. WALK AND CURB JOINTS SHALL BE ALIGNED.
4. SCORE MARKS TO MATCH EXISTING PATTERN.
5. IF SIDEWALK ABUTS EXISTING BUILDING PLACE EXPANSION JOINT.
6. ACCESS RAMPS SHALL CONFORM TO CALTRANS STANDARD PLAN A88A, A88B OR THE LATEST REVISION.

UTILITY BOX
OR VAULT

TREE WELL

FOC

LIP




BSW

PROPERTY LINE
(SEE NOTE 5)

2 CURB RAMP
LAYOUT
SEE ST-9.11

LEGEND:

- WEAKENED PLANE JOINT
- EXPANSION JOINT
- SCORE MARK
- BCR = BEGINNING OF CURB RETURN
- ECR = END OF CURB RETURN



SCALE: NTS







CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**CURB AND SIDEWALK
JOINTS**

STD DETAIL No.
ST 5



- NOTES:**
1. IN LOCATIONS WHERE TREE ROOTS ARE WITHIN 8" OF FINISHED GRADE, DELETE 4" AB AND PLACE 6" X 6" X 10 GA WIRE MESH IN CONCRETE. WHEN EXISTING SIDEWALK IS LESS THAN 4" THICK, DETAIL A MAY BE SUBSTITUTED FOR DOWELS.
 2. 4" THICK, DETAIL A MAY BE SUBSTITUTED FOR DOWELS.

SCALE: NTS



CITY OF ALBANY, CALIFORNIA


STANDARD DETAIL

APPROVED BY: *Ray Chan*

DATE: DECEMBER 2015


CURB, GUTTER & SIDEWALK REPAIRS

STD DETAIL No. ST 6



PLAN

SEE DETAIL A, ST 5 FOR ALTERNATIVE TO DOWELS



SECTION A-A

SCALE: NTS



CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**RESIDENTIAL
DRIVEWAY REPAIRS**


STD DETAIL No.
ST 7

LEGEND AND ABBREVIATION

	(PCC)=CONCRETE	(BSW)=BACK OF SIDEWALK
	(AB)=AGGREGATE BASE	R _L =PROPERTY LINE
	=SUBGRADE/EXIST. GRADE	FC=FACE OF CURB

NOTES

1. SUBGRADE SHALL BE NATIVE MATERIAL, 6" DEEP, 90% RELATIVE COMPACTION.
2. CUSHION MATERIAL SHALL BE CLASS 2 AGGREGATE BASE, PER CALTRANS STANDARD SPECIFICATIONS, SECTION 26; COMPACTED TO 95% R.C.
3. CONCRETE SHALL BE 520-C-2500, 4" MAXIMUM SLUMP.
4. CURB, GUTTER AND SIDEWALK TO BE PLACED MONOLITHICALLY WHERE POSSIBLE. WHERE NON-MONOLITHIC, PLACE DOWELS AND/OR KEYWAY PER ST 1.
5. PLACE 1/2" EXPANSION JOINT AT 200' SPACINGS AND AT RETURNS.
6. PLACE 3/4" DEEP WEAKENED PLANE JOINT AT 20' MAXIMUM SPACINGS THROUGH CURB AND GUTTER, AND 10' MAXIMUM SPACINGS THROUGH SIDEWALK, DRIVEWAY AND AT EDGES OF DRIVEWAYS AND AT 1/2 WIDTH FOR SIDEWALKS AND DRIVEWAYS OVER 10 FEET IN WIDTH.
7. PLACE SCORE LINES AT 5' MINIMUM SPACING BETWEEN WEAKENED PLANE JOINTS AND ALONG BACK OF CURB. MATCH EXISTING PATTERN IN RESIDENTIAL NEIGHBORHOODS.
8. PLACE NO. 4 REINFORCING STEEL BARS AT 18 INCHES EACH WAY IN INDUSTRIAL, COMMERCIAL AND STREET LEVEL DRIVEWAYS.
9. CONCRETE TO HAVE A SOFT BROOM FINISH. CLEAR CURING COMPOUND TO BE APPLIED PER MANUFACTURER'S SPECIFICATIONS.
10. WHEN REPLACING CURB, GUTTER, SIDEWALK, AND DRIVEWAY, MATCH EXISTING WIDTH AND SCORING. SAWCUTS SHALL BE AT JOINTS OR SCORE LINES. INSERT NO. 4 BY 18" LONG STEEL DOWELS AT 24" ON CENTER (2 MINIMUM FOR CURB AND GUTTER). ADD 1.5 LB. LAMPBLACK PER CUBIC YARD.
11. STAMP 3" HIGH LETTERS - "W"(WATER) AND "S"(SEWER) IN FACE OF CURB TO LOCATE LATERALS.
12. SAWCUT EXISTING A.C. PAVEMENT WITH POWER SAW.
13. ASPHALT CONCRETE SHALL BE 1/2" MAX AGGREGATE TYPE A PER CALTRANS SEC. 39, 3" MAXIMUM LIFTS.




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: Ray Chan
DATE: DECEMBER 2015

**LEGEND & NOTES- SIDEWALKS,
DRIVEWAYS AND CURB & GUTTER**

STD DETAIL No.
ST 8



CASE A



FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

CURB RAMP DETAILS
 (CASE A)

STD DETAIL No.
 ST 9.1



CASE B



SECTION B-B

DEPRESS ENTIRE SIDEWALK AS REQUIRED

FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**CURB RAMP DETAILS
(CASE B)**

STD DETAIL No.
ST 9.2




CASE C



SECTION C-C

FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

**CURB RAMP DETAILS
 (CASE C)**

STD DETAIL No.
ST 9.3



MODIFIED CASE C




SECTION C-C

1. WHEN CONFORMING TO SIDEWALK MAINTAIN MAXIMUM SLOPE OF 7.5% FOR 10 FEET THEN USE NECESSARY SLOPE ON PROPOSED SIDEWALK FOR 10 FEET TO CONFORM TO EXISTING SIDEWALK.
2. ENGINEERING DESIGN OF THE MODIFIED CASE C TO BE APPROVED BY THE CITY ENGINEER.

FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

CURB RAMP DETAILS
(MODIFIED CASE C)

STD DETAIL No.
ST 9.4




CASE D



SECTION A-A

FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

CURB RAMP DETAILS
 (CASE D)

STD DETAIL No.
 ST 9.5




CASE F



SECTION A-A

FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

CURB RAMP DETAILS
(CASE F)

STD DETAIL No.
ST 9.7



CASE G
SEE NOTE 4





FOR NOTES SEE SHEET ST 9.11

SCALE: NTS




CITY OF ALBANY, CALIFORNIA		STANDARD DETAIL	
APPROVED BY:	<i>Ray Chan</i>	CURB RAMP DETAILS (CASE G)	
DATE:	DECEMBER 2015	STD DETAIL No. ST 9.8	



FOR NOTES SEE SHEET ST 9.11

SCALE: NTS



CITY OF ALBANY, CALIFORNIA


STANDARD DETAIL

APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

**CURB RAMP DETAILS
 (CASE CM)**


STD DETAIL No.
ST 9.9

2.3" MIN AND 2.4" MAX
CENTER TO CENTER
SPACING




RAISED TRUNCATED DOME PATTERN (IN-LINE)
DETECTABLE WARNING SURFACE


SEE NOTE 10



RAISED TRUNCATED DOME



RETROFIT PAY LIMITS
EXISTING CURB AND SIDEWALK



GROOVING DETAIL

FOR NOTES SEE SHEET ST 9.11




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015


**CURB RAMP DETAILS - GROOVING AND
DOMES**

STD DETAIL No.
ST 9.10



DETAIL A
TYPICAL TWO-RAMP
CORNER INSTALLATION

SEE NOTE 1



DETAIL B
TYPICAL ONE-RAMP
CORNER INSTALLATION

SEE NOTES 1 AND 3

1. AS SITE CONDITIONS DICTATE, CASE A THROUGH CASE G CURB RAMPS MAY BE USED FOR CORNER INSTALLATIONS SIMILAR TO THOSE SHOWN IN DETAIL A AND DETAIL B. THE CASE OF CURB RAMPS USED IN DETAIL A DO NOT HAVE TO BE THE SAME. CASE A THROUGH CASE G CURB RAMPS ALSO MAY BE USED AT MID BLOCK LOCATIONS, AS SITE CONDITIONS DICTATE.
2. IF DISTANCE FROM CURB TO BACK OF SIDEWALK IS TOO SHORT TO ACCOMMODATE RAMP AND 4'-2" PLATFORM (LANDING) AS SHOWN IN CASE A, THE SIDEWALK MAY BE DEPRESSED LONGITUDINALLY AS IN CASE B, OR C OR MAY BE WIDENED AS IN CASE D.
3. WHEN RAMP IS LOCATED IN CENTER OF CURB RETURN, CROSSWALK CONFIGURATION MUST BE SIMILAR TO THAT SHOWN FOR DETAIL B.
4. AS SITE CONDITIONS DICTATE, THE RETAINING CURB SIDE AND THE FLARED SIDE OF THE CASE G RAMP SHALL BE CONSTRUCTED IN REVERSED POSITION.
5. IF LOCATED ON A CURVE, THE SIDES OF THE RAMP NEED NOT BE PARALLEL, BUT THE MINIMUM WIDTH OF THE RAMP SHALL BE 4'-2".
6. SIDE SLOPE OF RAMP FLARES VARY UNIFORMLY FROM A MAXIMUM OF 9.0% AT CURB TO CONFORM WITH LONGITUDINAL SIDEWALK SLOPE ADJACENT TO TOP OF THE RAMP, EXCEPT IN CASE C AND CASE F.
7. THE CURB RAMP SHALL BE OUTLINED, AS SHOWN, WITH A 1'-0" WIDE BORDER WITH," GROOVES APPROXIMATELY 3/4" ON CENTER. SEE GROOVING DETAIL.
8. TRANSITIONS FROM RAMPS AND LANDING TO WALKS, GUTTERS OR STREETS SHALL BE FLUSH (NO LIP) AND FREE OF ABRUPT CHANGES.
9. COUNTER SLOPES OF ADJOINING GUTTERS AND ROAD SURFACES IMMEDIATELY ADJACENT TO AND WITHIN 24 INCHES OF THE CURB RAMP SHALL NOT BE STEEPER THAN 1:20 (5.0%). GUTTER PAN SLOPE SHALL NOT EXCEED 1" OF DEPTH FOR EACH 2'-0" OF WIDTH.
10. CURB RAMPS SHALL HAVE A DETECTABLE WARNING SURFACE THAT EXTENDS THE FULL WIDTH AND 3'-0" DEPTH OF THE RAMP. A 4'-0" WIDE DETECTABLE WARNING SURFACE MAY BE USED ON A 4'-2" WIDE CURB RAMP. DETECTABLE WARNING SURFACES SHALL CONFORM TO THE REQUIREMENTS IN THE STANDARD SPECIFICATIONS.
11. THE EDGE OF THE DETECTABLE WARNING SURFACE NEAREST THE STREET SHALL BE BETWEEN 6" AND 8" FROM THE GUTTER FLOWLINE.
12. UTILITY PULL BOXES, MANHOLES, VAULTS AND ALL OTHER UTILITY FACILITIES WITHIN THE BOUNDARIES OF THE CURB RAMP WILL BE RELOCATED OR ADJUSTED TO GRADE BY THE OWNER PRIOR TO, OR IN CONJUNCTION WITH, CURB RAMP CONSTRUCTION.
13. DETECTABLE WARNING SURFACE MAY HAVE TO BE CUT TO ALLOW REMOVAL OF UTILITY COVERS WHILE MAINTAINING FULL DETECTABLE WARNING WIDTH AND DEPTH.




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

CURB RAMP DETAILS
(NOTES)

STD DETAIL No.
ST 9.11



TYPE A PASSAGEWAY



SECTION B-B

FOR NOTES SEE SHEET ST 10.4

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**ISLAND PASSAGEWAY DETAILS
(TYPE A)**

STD DETAIL No.
ST 10.1



TYPE B PASSAGEWAY



FOR NOTES SEE SHEET ST 10.4

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

ISLAND PASSAGEWAY DETAILS
(TYPE B)

STD DETAIL No.
ST 10.2




TYPE C PASSAGEWAY



SECTION B-B

FOR NOTES SEE SHEET ST 10.4

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

ISLAND PASSAGEWAY DETAILS
 (TYPE C)


STD DETAIL No.
 ST 10.3



RETROFIT PAY LIMITS


Existing curb and sidewalk

APPROXIMATELY ?"



GROOVING DETAIL


2.3" Min AND 2.4" Max
CENTER TO CENTER
SPACING



RAISED TRUNCATED DOME PATTERN (IN-LINE)

DETECTABLE WARNING SURFACE


See Note 10



RAISED TRUNCATED DOME

NOTES:

1. SIDEWALK, RAMP AND PASSAGEWAY THICKNESS, "T", SHALL BE 3" MINIMUM.
2. FOR DETAILS OF GROOVING USED WITH CASE CM CURB RAMP, SEE STANDARD DETAIL ST 7A SHEET 8.
3. FOR DETAILS OF DETECTABLE WARNING SURFACES, SEE REVISED STANDARD DETAIL 7A.
4. WHERE AN ISLAND PASSAGEWAY LENGTH IS GREATER THAN OR EQUAL TO 6'-0", BUT LESS THAN 8'-0", EACH DETECTABLE WARNING SURFACE SHALL EXTEND THE FULL WIDTH AND 2'-0" DEPTH OF THE PASSAGEWAY LENGTH. WHERE AN ISLAND PASSAGEWAY LENGTH IS GREATER THAN OR EQUAL TO 8'-0", EACH DETECTABLE WARNING SURFACE SHALL EXTEND THE FULL WIDTH AND 3'-0" DEPTH OF THE PASSAGEWAY LENGTH. A 4'-0" WIDE DETECTABLE WARNING SURFACE MAY BE USED ON A 4'-2" WIDE ISLAND PASSAGEWAY.
5. FOR CASE CM CURB RAMP, THE EDGE OF THE DETECTABLE WARNING SURFACE NEAREST THE STREET SHALL BE BETWEEN 6" AND 8" FROM THE GUTTER FLOW LINE. REFER TO STANDARD DETAIL ST 7A, SHEET 8 FOR DETAILS.
6. TRANSITIONS FROM RAMPS TO WALKS, GUTTERS OR STREETS SHALL BE FLUSH (NO LIP) AND FREE OF ABRUPT CHANGES.
7. UTILITY PULL BOXES, MANHOLES, VAULTS AND ALL OTHER UTILITY FACILITIES WITHIN THE BOUNDARIES OF THE CURB RAMP WILL BE RELOCATED OR ADJUSTED TO GRADE BY THE OWNER PRIOR TO, OR IN CONJUNCTION WITH, CURB RAMP CONSTRUCTION.
8. DETECTABLE WARNING SURFACE MAY HAVE TO BE CUT TO ALLOW REMOVAL OF UTILITY COVERS WHILE MAINTAINING FULL DETECTABLE WARNING WIDTH AND DEPTH. FOR ADDITIONAL CURB RAMP DETAILS, SEE STANDARD DETAIL ST 7A.



CITY OF ALBANY, CALIFORNIA


STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**ISLAND PASSAGEWAY DETAILS AND
NOTES**

STD DETAIL No.
ST 10.4


TWO 8" HIGH SIGNS
MOUNTED AT RIGHT ANGLES TO
EACH OTHER ON TOP OF POLE



ALL OTHER SIGNS - MINIMUM 7' FROM GROUND LEVEL TO BOTTOM EDGE OF SIGN

ALL SIGNS TO BE MOUNTED ON UNISTRUT TELES PAR OR WESTERN HIGHWAY 1-3/4" SQUARE TUBULAR SIGN POLES. COLOR: POWDER FINISH DARK GREEN. POLES TO BE SECURED IN GROUND USING UNISTRUT TELES PAR OR WESTERN HIGHWAY SYSTEM. SIGNS TO BE ATTACHED TO POLES, AND POLES ATTACHED TO ANCHORS AND COLLARS, USING UNISTRUT OR WESTERN HIGHWAY PLATED STEEL OR ALUMINUM RIVETS.

SCALE: NTS





CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

STREET & TRAFFIC SIGN
MOUNTING STANDARDS


STD DETAIL No.
ST 11



TYPICAL SECTION

NOTE: ANCHOR SLEEVE + STIFFNER = ANCHOR ASSEMBLY

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

SIGN ANCHOR
DETAIL

STD DETAIL No.
ST 12



TRENCH SURFACE RESTORATION DETAIL




DETAIL A
GUTTER LIP PAVING

NOTES:

1. MATCH EXISTING ASPHALT THICKNESS PLUS 1" (3" THICK MINIMUM).
2. WHEN APPROVED BY THE ENGINEER CDF MAY BE USED AS AN ALTERNATE FOR AGG BASE FOR SHALLOW PIPELINES PROVIDING MEASURES ARE TAKEN TO PREVENT PIPE FLOTATION.
3. THE FINAL LIFT OF AC IN STREETS SHALL BE COMPACTED WITH A ROLLER APPROVED BY THE ENGINEER.
4. WHEN THE TRENCH PARALLELS CURB AND THE NEAREST TRENCH LINE IS LESS THAN 2 FEET FROM THE GUTTER LIP OR CURB WHEN NO GUTTER EXISTS, ALL EXISTING ASPHALT CONCRETE SHALL BE REPLACED TO THE GUTTER LIP. FOR GUTTER LIP PAVING DETAIL SEE DETAIL "A".
5. ASPHALT CONCRETE SHALL BE 1/2" TYPE A ASPHALT CONCRETE UNLESS OTHERWISE SPECIFIED OR DIRECTED BY THE CITY ENGINEER.
6. THE ASPHALT CONCRETE SHALL BE CUT THROUGH THE FULL DEPTH OF EXISTING ASPHALT CONCRETE TO A NEAT STRAIGHT LINE AT LEAST 6" OUTSIDE THE TRENCH LINE. PAVEMENT EDGES DAMAGED DURING CONSTRUCTION SHALL BE RE-CUT TO NEAT LINES PRIOR TO PAVING. POINT BINDER (TACK COAT) SHALL BE APPLIED TO ALL VERTICAL SURFACES IN OCCORDANCE WITH THE LATEST EDITION OF CALTRANS STANDARD SPECIFICATIONS.
7. THE EXISTING ASPHALT CONCRETE OUTSIDE THE TRENCH LINE MAY BE GROUND TO A MINIMUM DEPTH OF 0.20 FEET TO A NEAT STRAIGHT LINE AT LEAST 6" OUTSIDE THE TRENCH LNE. THE EXISTING ASPHALT CONCRETE AT THE TRENCH LINES SHALL BE CUT THROUGH THE FULL DEPTH OF THE EXISTING ASPHALT CONCRETE TO A NEAT STRAIGHT LINE. ANY PAVEMENT EDGES, INCLUDING GROUND EDGES, DAMAGED DURING CONSTRUCTION SHALL BE RE-CUT OR RE-GROUND TO NEAT LINES PRIOR TO PAVING. POINT BINDER (TACT COAT) SHALL BE APPLIED TO ALL VERTICAL SURFACES IN OCCORDANCE WITH LATEST EDITION OF CALTRANS STANDARD SPECIFICATIONS.

SCALE: NTS







CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**TRENCH SURFACE
RESTORATION DETAIL**

STD DETAIL No.
ST 13



SCALE: NTS



CITY OF ALBANY, CALIFORNIA


STANDARD DETAIL

APPROVED BY: *Ray Chan*

DATE: DECEMBER 2015

SIDEWALK DRAIN
RESIDENTIAL LOTS


STD DETAIL No.
ST 14



NOTES:

1. SIGNS SHALL HAVE SERIES D BLACK LETTERS ON REFLECTIVE WHITE BACKGROUND PLACE TYPE I SIGNS IN A VISIBLE LOCATION.
2. SIGN TO BE PLACED ON EITHER SIDE OF WORK AREA.
3. LOCATION OF SIGN SHALL BE AS APPROVED BY THE CITY ENGINEER.

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

CONSTRUCTION WARNING SIGN

STD DETAIL No.
ST 15



SIDEWALK ELEVATION VIEW

NOTES:

1. THE UNIT FOR PAYMENT SHALL BE INCH-FOOT (IN.-FT)
2. MEASUREMENT FOR PAYMENT SHALL BE MADE BY MULTIPLYING THE LENGTH OF THE CUT BY THE AVERAGE DEPTH OF THE CUT.
3. CUT SHALL EXTEND FOR FULL WIDTH OF SIDEWALK, EDGE TO EDGE
4. PROTECT CITIZENS AND ALL PRIVATE AND PUBLIC FACILITIES FROM DAMAGE OR HARM.
5. LEVEL AND RESHAPE EXISTING SOD AS NECESSARY.
6. SITE CLEAN-UP SHALL BE ACCOMPLISHED AS SOON AS SAWCUTTING OPERATION IS COMPLETE.
7. ONLY THOSE PANELS WHICH ARE IN GOOD CONDITION AND NOT SUBJECT TO REPLACEMENT IN ACCORDANCE WITH PLAN No. 291 (DEFECTIVE CONCRETE) OF THE APWA MANUAL OF STANDARD PLANS SHALL BE SAWCUT.

SCALE: NTS



CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL



APPROVED BY: Ray Chan
 DATE: DECEMBER 2015

SIDEWALK TRIP HAZARD REMOVAL

STD DETAIL No.
ST 16



NPDES MEDALLION



PLAN:

1. ORIENT MEDALLION TEXT TO BE READ FROM THE SIDEWALK. EPOXY MEDALLION WITH PREMIUM POLYURETHANE CONSTRUCTION ADHESIVE. ADHESIVE MUST DEVELOP FULL STRENGTH IN 24 HOURS OR LESS AND MEET ASTM C-557, DS498.
2. MEDALLION SHALL BE LOCATED BEHIND THE BACK OF CURB IN LOCATIONS WITH EXISTING OR PLANNED RED CURBS.

SCALE: NTS





CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015


NPDES MEDALLION

STD DETAIL No.
ST 17



NOTES

1. FOR ADDITIONAL CAPACITY, ADJACENT DRAINS MAY BE INSTALLED AND THE WIDTH OF INLET SHALL BE INCREASED AS REQUIRED. MINIMUM CLEAR DISTANCE BETWEEN DRAINS AT CURB FACE SHALL BE 6 INCHES.
2. ADJACENT DRAINS SHALL BE THE SAME TYPE
3. IN TRAFFIC AREAS, THE GRATE SHALL BE US CONCRETE PRECAST GROUP (CENTRAL PRECAST) HEAVY GRATE, OR APPROVED EQUAL.
4. IN NON-TRAFFIC AREAS THE GRATE SHALL BE US CONCRETE PRECAST GROUP (CENTRAL PRECAST) STANDARD GRATE, OR APPROVED EQUAL.
5. EACH GRATE SHALL BE PROVIDED WITH A MINIMUM OF TWO (2) LOCKING DEVICES.



SCALE: NTS

CITY OF ALBANY, CALIFORNIA



STANDARD DETAIL



APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

SIDEWALK CROSS DRAIN


STD DETAIL No.
ST 18



NOTES:

1. ALL NOTES AND DIMENSION SYSMETRICAL ABOUT CENTERLINE
2. PROVIDE A SMOOTH TRANSITION FROM VALLEY TO END OF RETURN.
3. ALL INTERSECTIONS TO HAVE ACCESS RAMPS DESIGNED IN ACCORDANCE WITH ADA STANDARDS

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
 DATE: DECEMBER 2015

**CONCRETE VALLEY GUTTER
 AND APRON**

STD DETAIL No.
ST 19



NOTES:

1. RELOCATE SIDEWALK OBSTRUCTIONS BEHIND THE SIDEWALK AREA WITHIN A PUBLIC SERVICE EASEMENT
2. WHEN OBSTRUCTIONS CANNOT BE MOVED AND A 3-FOOT CLEAR AREA BETWEEN AN OBSTRUCTION AND THE EDGE OF SIDEWALK IS NOT AVAILABLE, A RETROFIT SIDEWALK FLARE MAY BE USED. FLARE CONSTRUCTION SHALL CONFORM TO STANDARD CITY SIDEWALK REQUIREMENTS.
3. USE OF THE SIDEWALK FLARE DETAIL SHALL BE APPROVED BY THE CITY ENGINEER FOR SPECIAL RETROFIT SITUATIONS ONLY. THIS DETAIL WILL NOT BE ALLOWED AS A CORRECTION IMPROPERLY PLACED FACILITIES.

SCALE: NTS



CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015


**RETROFIT SIDEWALK FLARE
FOR OBSTRUCTIONS**

STD DETAIL No.
ST 20


CONST JOINT FINISH SMOOTH
AND PROVIDE BOND BREAKER
FOR WEAKENED PLAN

USE ONLY WITH STANDARD
TRACT MONUMENT DISC
INSTALLATION

TO PROVIDE FOR DRAINAGE,
NO CONCRETE WILL BE
ALLOWED IN THIS AREA



PLAN SECTION OF POST



ELEVATION

NOTES:

MONUMENT FRAMES AND COVERS SHALL BE:

1. NEENAH FOUNDRY COMPANY, CATALOG NO. R-1975-B, LID TYPE C WITH MONUMENT ON THE LID.
2. CHRISP CASTING PERT NO. 9279, +277M
3. OTHER MANUFACTURERS MODELS APPROVED BY THE CITY OF ALBANY DEPARTMENT OF PUBLIC WORKS SHALL BE EQUAL IN SERVICE AND FUNCTION. EACH COVER SHALL BE GROUND OR OTHERWISE FINISHED SO THAT IT WILL FIT IN ITS FRAME WITHOUT ROCKING. CONCRETE SHALL BE EITHER CLASS A OR CLASS B, POURED IN PLACE AGAINST THE EXISTING GROUND.

(A) INSTALL 3 OR MORE 1/4" X 3" METAL DOWELS EXTENDING 1' ABOVE SURFACE OF CONCRETE. BEND AS SHOWN.

(B) PROVIDE A FORM OF SHEET METAL OR 3/32" THICK WAX-IMPREGNATED PAPER.

SCALE: NTS




CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL


APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

**CONCRETE MONUMENT SECTION
WITH DISC**

STD DETAIL No.
ST 21




BRACED LINE POST INSTALLATION
BRACED LINE POST AT INTERVALS NOT EXCEEDING 1000'



CHAIN LINK GATE INSTALLATION

NOTES AND SCHEDULE ON SHEET 2

SCALE: NTS



CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: *Ray Chan*
DATE: DECEMBER 2015

CHAIN LINK
FENCE AND GATE

STD DETAIL No.
ST 22.1

GATE POST			
FENCE HEIGHT	GATE WIDTHS	ROUND OD PIPE	WEIGHT (lb/ft)
6'-0" AND LESS	UP THRU 6'-0"	2.875"	5.80
	OVER 6'-0" THRU 12'-0"	4.500"	10.80
	OVER 12'-0" THRU 18'-0"	5.563"	14.63
	OVER 18'-0" TO 24'-0" Max	6.625"	18.99
OVER 6'-0" TO 8'-0" Max	UP THRU 6'-0"	3.500"	7.58
	OVER 6'-0" THRU 12'-0"	5.563"	14.63
	OVER 12'-0" THRU 18'-0"	6.625"	18.99
	OVER 18'-0" TO 24'-0" Max	8.625"	28.58


ABOVE POST DIMENSIONS AND WEIGHTS ARE MINIMUMS. LARGER SIZES MAY BE USED UPON APPROVAL.

TYPICAL MEMBER DIMENSIONS (See Notes)										
FENCE HEIGHT	LINE POSTS				END, LATCH AND CORNER POSTS		BRACES			
	ROUND OD PIPE	WEIGHT (lb/ft)	ROLL FORMED		ROUND OD PIPE	WEIGHT (lb/ft)	ROUND OD PIPE	WEIGHT (lb/ft)	ROLL FORMED	
			U	□					U	□
			SECTION	WEIGHT (lb/ft)					SECTION	WEIGHT (lb/ft)
6'-0" AND LESS	1.900"	2.72	1.875" x 1.625"	1.85	2.375"	3.65	1.66"	2.27	1.625" x 1.25"	1.35
OVER 6'-0" TO 8'-0" Max	2.375"	3.65	2.25" x 1.70"	2.78	2.875"	5.80	1.66"	2.27	1.625" x 1.25"	1.35

NOTES:

1. THE TABLE BELOW SHOWS MINIMUM SIZED POSTS AND BRACES COMPLYING WITH THE SPECIFICATIONS. LARGER OR HEAVIER POST AND BRACE SIZES MAY BE USED UPON APPROVAL
2. SECTIONS SHOWN IN THE TABLES MUST ALSO COMPLY WITH THE STRENGTH REQUIREMENTS AND OTHER PROVISIONS OF THE SPECIFICATIONS.
3. OTHER SECTIONS WHICH COMPLY WITH THE STRENGTH REQUIREMENTS AND OTHER PROVISIONS OF THE SPECIFICATIONS MAY BE USED UPON APPROVAL.
4. OPTIONS EXERCISED SHALL BE UNIFORM ON ANY ONE PROJECT.
5. OFFSET TO BE 2'-0" AT MONUMENT LOCATIONS, MEASURED AT RIGHT ANGLES TO R/W LINES. TAPER TO ACHIEVE OFFSET TO BE AT LEAST 20'-0" LONG.
6. SEE REVISED STANDARD PLAN RSP A85B FOR BRACE, STRETCHER BAR, AND TRUSS TIGHTENER DETAILS.

SCALE: NTS



CITY OF ALBANY, CALIFORNIA

STANDARD DETAIL

APPROVED BY: Ray Chan
DATE: DECEMBER 2015

**CHAIN LINK FENCE
AND GATE - NOTES**

STD DETAIL No.
ST 22.2